COUNTY OF SUFFOLK

STEVE LEVY
SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF PUBLIC WORKS

GILBERT ANDERSON, P.E.
COMMISSIONER

JAMES PETERMAN, P.E.
ACTING CHIEF DEPUTY COMMISSIONER

December 2, 2011

TO ALL PROSPECTIVE BIDDERS FOR:

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM
THE VICINITY OF BLUE JAY DRIVE
TO THE VICINITY OF CR 13, FIFTH AVENUE
TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539

AMENDMENT NO. TWO (2)

PLAN CLARIFICATIONS:

- The detail entitled *DETAIL OF RECHARGE BASIN OUTLET PROTECTION* on plan sheet 8 contains an incorrect reference to Item 80 – Stone Outlet Protection. The cost associated with furnishing and installing the Stone Outlet Protection shall be paid for under attached Item 80C – Rip Rap. This is a new item and was not included on the original Bid Form.

- The detail entitled *DETAIL OF RECHARGE BASIN OUTLET PROTECTION* on plan sheet 8 contains an incorrect reference to Item 17 – Concrete Cut Off Wall. The cost associated with furnishing and installing the Concrete Cut Off Wall shall be included under Item 14ESS-30 or Item 14ESS-36, Reinforced Concrete Pipe Class IV End Section, 30" or 36" Diameter, as identified on the Construction Plans.

- Item 105DW – Detectable Warning Field, is referenced on the legend of the Construction Plans, but was omitted from the Bid Form. These units shall be installed at each new curb ramp in accordance with NYSDOT Standard Sheets 608-01 – Standard Curb Ramp Details. Item 105DW is attached for your reference.

BID FORM MODIFICATIONS:

- Please replace ***all*** original Bid Form pages P1 through P29 with the enclosed revised Bid Form pages P1 through P29. The Bid Form package should not be unbound – simply cross out the existing pages and place the attached pages within the Bid Form package. The following changes have been made:
  - The quantity for Item 80C is 85 Tons for all bid alternates.
  - The quantity for Item 105DW is 700 square feet for Bid Alternates 1 (Base + Option A) and 3 (Base + Option C), and 800 square feet for Bid Alternates 2 (Base + Option B) and 4 (Base + Option D).

William Hillman, P.E., Chief Engineer

NOTE: Upon receipt of this amendment, please sign and fax to: 631-852-4079

FIRM: _____

SIGNED: _____

TITLE: _____

WH:jd
attach.
cc: James K. Peterman, P.E., Acting Chief Deputy Commissioner
Paul G. McMahon, P.E., Director of Consultant Management
Jeff Dawson, P.E., Senior Civil Engineer

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
2AU	100	CY,REMOVAL OF UNSUITABLE MATERIAL PER CY				
14ESS-30	1	EA,REINFORCED CONCRETE PIPE CLASS IV END SECTION, 30" DIAMETER PER EA				
14ESS-36	1	EA,REINFORCED CONCRETE PIPE CLASS IV END SECTION, 36" DIAMETER PER EA				
14S-18	3500	LF,REINFORCED CONCRETE PIPE, CLASS IV, 18" DIA. PER LF				
14S-24	2600	LF,REINFORCED CONCRETE PIPE, CLASS IV, 24" DIA. PER LF				
14S-30	1000	LF,REINFORCED CONCRETE PIPE, CLASS IV, 30" DIA. PER LF				
14S-36	74	LF,REINFORCED CONCRETE PIPE, CLASS IV, 36" DIA. PER LF				
14WS-14	70	LF,REINFORCED HORIZONTAL ELLIPTICAL CONCRETE PIPE, CLASS HE-IV, 23"X14" PER LF				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
14WS-19	200	LF,REINFORCED HORIZONTAL ELLIPTICAL CONCRETE PIPE CLASS HE-IV, 30"X19" PER LF				
33DA	2	EA,ANCHORAGE UNITS FOR HEAVY POST BLOCKED OUT CORRUGATED BEAM GUIDE RAILING PER EA				
33PS	100	LF,HEAVY POST, PLASTIC & SYNTHETIC BLOCKOUT GALVANIZED CORRUGATED STEEL BEAM GUIDE RAILING PER LF				
51PAX	1	LS,ASPHALT AND FUEL PRICE ADJUSTMENT One Dollar PER LS	$1	00	$1	00
80C	80	TON,RIP RAP PER TON				
93TE	1	EA,TEMPORARY STONE CONSTRUCTION ENTRANCE PER EA				
100D	4	EA,LEACHING BASIN, TYPE D PER EA				
100DX	11	EA,LEACHING BASIN TYPE 'DX' PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
102A	100	LF,CATCH BASIN TYPE 'A' PER LF				
102B	90	LF,CATCH BASIN TYPE 'B' PER LF				
102C	50	LF,MANHOLE TYPE 'C' PER LF				
102CH	6	LF,MANHOLE, TYPE CH PER LF				
106DG-6	2	EA,DOUBLE-SWING FENCE GATE WITH VINYL COATED CHAIN LINK FENCE FABRIC PER EA				
106VC-6	1260	LF,VINYL COATED CHAIN LINK FENCING (PARK FENCING), 6 FEET HIGH PER LF				
106VCL-6G6	1500	LF,VINYL COATED CHAIN LINK FENCING PER LF				
123ECM	1	LS,PLACING EROSION CONTROL MAT AND SEEDING ON PREPARED AREAS PER LS				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
127-204	50	EA,CUPRESSOCYPARIS LEYLANDI, LEYLAND CYPRESS, 5' - 6' HT., B&B PER EA				
645.5202	160	SF,GROUND MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 30 SF WITH Z-BARS, HIGH VISIBILITY SHEETING PER SF				
645.82	2	EA,TYPE B SIGN POST PER EA				
645.85	34	EA,POLE-MOUNTED SIGN SUPPORT SYSTEM (BAND MOUNTING) PER EA				
648.50010008	40	CY,TEST PIT EXCAVATION (SUBSURFACE EXPLORATIONS) PER CY				
685TR	8000	LF,REMOVAL OF THERMOPLASTIC MARKINGS FOR PER LF				
685WL	40	EA,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT LETTERS FOR PER EA				
1065	1	LS,RELOCATING DECORATIVE STREET LIGHTING PER LS				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
T1-1XL	500	LF,AERIAL CABLE, SELF SUPPORTING, 2 CONDUCTORS #4 AWG (TERRIER XL) PER LF				
T4E	8	EA,STEEL POLE 30 FEET, DESIGN LOAD 7,700 lbs PER EA				
T4G	4	EA,STEEL POLES 32 FT, DESIGN LOAD 7,790 lbs PER EA				
T4P10	12	EA,SIGNAL POST 10 FT PER EA				
T4TC	2	EA,TIMBER POLE 25 FT PER EA				
T5-1	40	LF,SIGNAL CABLE, 2 CONDUCTORS #6 AWG PER LF				
T5-1B	210	LF,SIGNAL CABLE, 2 CONDUCTORS #4 AWG PER LF				
T5-2	3900	LF,SIGNAL CABLE, 2 CONDUCTORS #14 AWG PER LF				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
T5-5	4900	LF,SIGNAL CABLE, 5 CONDUCTORS #14 AWG PER LF				
T5-20	900	LF,SIGNAL CABLE, 20 CONDUCTORS #14 AWG PER LF				
T5-I	80	LF,INSTALL TRAFFIC SIGNAL CABLE PER LF				
T5XC	7200	LF,COMMUNICATION CABLE, 6 PAIR, #19 AWG PER LF				
T6-2	260	LF,STEEL CONDUIT, 1 INCH DIAMETER PER LF				
T6-4	40	LF,STEEL CONDUIT, 1 1/2 INCH DIAMETER PER LF				
T6-5	6000	LF,STEEL CONDUIT, 2 INCH DIAMETER PER LF				
T6-7	1220	LF,STEEL CONDUIT, 3 INCH DIAMETER PER LF				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
T6B-7	50	LF,JACKING STEEL CONDUIT, 3 INCH DIAMETER PER LF				
T8LB	6	EA,8" TRAFFIC SIGNAL LOUVERS PER EA				
T9S-1	2	EA,SOLID STATE TIME SWITCH PER EA				
T10CB	32	EA,LED PEDESTRIAN SIGNAL WITH COUNTDOWN (16"x18") PER EA				
T12LED	147	EA,LED TRAFFIC SIGNAL SECTION PER EA				
T14A	6	EA,SPAN WIRE ASSEMBLY, 1/4" DIAMETER PER EA				
T14C	6	EA,SPAN WIRE ASSEMBLY, 7/16" DIAMETER PER EA				
T16N2070B12	6	EA,2070 MICROCOMPUTER CONTROLLER WITH CABINET, 12 POSITION PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
T17	2	EA,FLASHER WITH CABINET PER EA				
T19-OC3	1950	LF,OPTICAL DETECTION CABLE, 3 COND. PER LF				
T20	50	EA,PULLBOX PER EA				
T20A	1	EA,ADJUST PULLBOX TO GRADE PER EA				
T21LWS	2590	LF,ROADWAY LOOP, SPECIAL PER LF				
T21SC	2650	LF,SHIELDED LEAD-IN CABLE PER LF				
T24C	25	EA,PEDESTRIAN COUNTDOWN PUSH BUTTON ASSEMBLY PER EA				
T30S	36	INT-MONTH,MAINTAIN TRAFFIC SIGNAL CONTROL EQUIPMENT PER INT-MONTH				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

BASE ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
T31S-A	10	EA,REMOVE TRAFFIC POLE OR CONTROLLER FOUNDATION PER EA				
T31S-B	8	EA,REMOVE TRAFFIC POLE STEEL OR TIMBER PER EA				
T31S-C	17	EA,REMOVE TRAFFIC SIGNAL PULLBOX PER EA				
T31S-D	5	EA SIGNAL,REMOVE MISCELLANEOUS SIGNAL EQUIPMENT PER EA SIGNAL				
T31S-E	3400	LF,REMOVE SIGNAL CABLE PER LF				
T71	1	EA,OVERHEAD TRAFFIC CONTROL SIGNS PER EA				
		Subtotal Base Items:	$			

SUBTOTAL ITEMS W/MOBILIZATION IN WORDS: _____

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'A' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
1SB	1	LS,CLEARING AND GRUBBING PER LS				
2AS	1	LS,UNCLASSIFIED EXCAVATION PER LS				
4S	3525	CY,STABILIZED SOIL AGGREGATE SUBBASE PER CY				
6EOS-B	1	LS,ENGINEER'S OFFICE, TYPE B PER LS				
30C	61500	LB,FRAMES AND GRATES - CASTINGS PER LB				
30F	18500	LB,FRAMES AND GRATES FABRICATED PER LB				
51D	130	TON,ASPHALT CONCRETE FOR DRIVEWAYS PER TON				
51FX	13400	TON,ASPHALT CONCRETE PER TON				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'A' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
51PRA	32300	SY,COLD MILLING, SHAPING AND REMOVAL OF PER SY				
70B	2850	GAL,BITUMINOUS MATERIAL EMULSION TACK COAT PER GAL				
76SX	1	LS,MAINTENANCE AND PROTECTION OF TRAFFIC PER LS				
97A	13070	LF,CONCRETE CURB, TYPE 'A' PER LF				
97B	60	LF,CONCRETE CURB, TYPE 'B' PER LF				
103	1	EA,ALTERING CATCH BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				
103AD	7	EA,ADJUSTING CATCH BASINS, LEACHING BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				
104B	15	EA,CLEANING EXISTING CATCH BASINS, MANHOLES, DROP INLETS, AND LEACHING BASINS PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'A' ITEMS

ITEM NO.	APPROX QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
104C	450	LF,CLEANING CULVERTS AND STORM DRAINAGE PIPE PER LF				
105DW	700	SF,EMBEDDED DETECTABLE WARNING UNITS PER SF				
105S4	3300	SY,CONCRETE SIDEWALK - 4" THICK PER SY				
105S6	2100	SY,CONCRETE SIDEWALK - 6" THICK PER SY				
116	1	LS,PROJECT SURVEY AND STAKEOUT FOR PER LS				
121AS	400	CY,TOPSOIL FURNISHED AND PLACED PER CY				
123LS	1	LS,SEEDING ON PREPARED AREAS PER LS				
205	15300	LF,SAWCUTTING PAVEMENT AND SIDEWALK PER LF				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'A' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
645.5102	370	SF,GROUND MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 30 SF WITH Z-BARS PER SF				
645.81	100	EA,TYPE "A" SIGN POSTS PER EA				
647.01	47	EA,REMOVAL OF SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.11	9	EA,RELOCATING SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.13	1	EA,RELOCATING TRAFFIC SIGNS, SIZE 'B' (21 TO 40 SF) PER EA				
685W	59900	LF,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
685WS	85	EA,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT SYMBOLS FOR PER EA				
685Y	41400	LF,YELLOW THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'A' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
		Subtotal Option 'A' Items:	$			
		Subtotal Base Items:	$			
		Subtotal for Alternate 1: Base Items Plus Option 'A' Items:	$			
1M	NEC	MOBILIZATION MUST NOT EXCEED 4% OF SUBTOTAL SHOWN ABOVE. SEE SPECIFICATION FOR THIS ITEM. PER LS				
		Total Sum Bid for Alternate 1: Base Items Plus Option 'A' Items Plus Mobil.:	$			

SUBTOTAL ITEMS W/MOBILIZATION IN WORDS: _____

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'B' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
1SB	1	LS,CLEARING AND GRUBBING PER LS				
2AS	1	LS,UNCLASSIFIED EXCAVATION PER LS				
4S	3650	CY,STABILIZED SOIL AGGREGATE SUBBASE PER CY				
6EOS-B	1	LS,ENGINEER'S OFFICE, TYPE B PER LS				
30C	61500	LB,FRAMES AND GRATES - CASTINGS PER LB				
30F	18500	LB,FRAMES AND GRATES FABRICATED PER LB				
51D	140	TON,ASPHALT CONCRETE FOR DRIVEWAYS PER TON				
51FX	13760	TON,ASPHALT CONCRETE PER TON				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'B' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
51PRA	32300	SY,COLD MILLING, SHAPING AND REMOVAL OF PER SY				
70B	2890	GAL,BITUMINOUS MATERIAL EMULSION TACK COAT PER GAL				
76SX	1	LS,MAINTENANCE AND PROTECTION OF TRAFFIC PER LS				
80C	800	TON,RIP RAP PER TON				
97A	15170	LF,CONCRETE CURB, TYPE 'A' PER LF				
97B	2060	LF,CONCRETE CURB, TYPE 'B' PER LF				
103	1	EA,ALTERING CATCH BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				
103AD	7	EA,ADJUSTING CATCH BASINS, LEACHING BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'B' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
104B	15	EA,CLEANING EXISTING CATCH BASINS, MANHOLES, DROP INLETS, AND LEACHING BASINS PER EA				
104C	450	LF,CLEANING CULVERTS AND STORM DRAINAGE PIPE PER LF				
105DW	800	SF,EMBEDDED DETECTABLE WARNING UNITS PER SF				
105S4	3600	SY,CONCRETE SIDEWALK - 4" THICK PER SY				
105S6	2490	SY,CONCRETE SIDEWALK - 6" THICK PER SY				
105SCI4	980	SY,INTEGRALLY COLORED AND IMPRINTED CONCRETE SIDEWALKS, 4" THICK PER SY				
105SCI6	320	SY,INTEGRALLY COLORED AND IMPRINTED CONCRETE SIDEWALKS, 6" THICK PER SY				
116	1	LS,PROJECT SURVEY AND STAKEOUT FOR PER LS				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'B' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
121AS	540	CY,TOPSOIL FURNISHED AND PLACED PER CY				
123LS	1	LS,SEEDING ON PREPARED AREAS PER LS				
205	19300	LF,SAWCUTTING PAVEMENT AND SIDEWALK PER LF				
645.5102	420	SF,GROUND MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 30 SF WITH Z-BARS PER SF				
645.5201	20	SF,GROUND MOUNTED SIGN PANELS W/O Z BARS, HIGH VISIBILITY SHEETING PER SF				
645.81	120	EA,TYPE "A" SIGN POSTS PER EA				
647.01	59	EA,REMOVAL OF SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.11	11	EA,RELOCATING SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'B' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
647.13	2	EA,RELOCATING TRAFFIC SIGNS, SIZE 'B' (21 TO 40 SF) PER EA				
685W	62100	LF,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
685WS	85	EA,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT SYMBOLS FOR PER EA				
685Y	43000	LF,YELLOW THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
		Subtotal Option 'B' Items:	$			
		Subtotal Base Items:	$			
		Subtotal for Alternate 2: Base Items Plus Option 'B' Items:	$			
1M	NEC	MOBILIZATION MUST NOT EXCEED 4% OF SUBTOTAL SHOWN ABOVE. SEE SPECIFICATION FOR THIS ITEM. PER LS				
		Total Sum Bid for Alternate 2: Base Items Plus Option 'B' Items Plus Mobil.:	$			

SUBTOTAL ITEMS W/MOBILIZATION IN WORDS: _____

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'C' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
1SB	1	LS,CLEARING AND GRUBBING PER LS				
2AS	1	LS,UNCLASSIFIED EXCAVATION PER LS				
4S	3525	CY,STABILIZED SOIL AGGREGATE SUBBASE PER CY				
6EOS-B	1	LS,ENGINEER'S OFFICE, TYPE B PER LS				
30C	70200	LB,FRAMES AND GRATES - CASTINGS PER LB				
30F	21500	LB,FRAMES AND GRATES FABRICATED PER LB				
51D	150	TON,ASPHALT CONCRETE FOR DRIVEWAYS PER TON				
51FX	16080	TON,ASPHALT CONCRETE PER TON				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'C' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
51PRA	50000	SY,COLD MILLING, SHAPING AND REMOVAL OF PER SY				
70B	3780	GAL,BITUMINOUS MATERIAL EMULSION TACK COAT PER GAL				
76SX	1	LS,MAINTENANCE AND PROTECTION OF TRAFFIC PER LS				
80C	700	TON,RIP RAP PER TON				
97A	13180	LF,CONCRETE CURB, TYPE 'A' PER LF				
97B	170	LF,CONCRETE CURB, TYPE 'B' PER LF				
103	2	EA,ALTERING CATCH BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				
103AD	8	EA,ADJUSTING CATCH BASINS, LEACHING BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'C' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
104B	26	EA,CLEANING EXISTING CATCH BASINS, MANHOLES, DROP INLETS, AND LEACHING BASINS PER EA				
104C	2780	LF,CLEANING CULVERTS AND STORM DRAINAGE PIPE PER LF				
105DW	700	SF,EMBEDDED DETECTABLE WARNING UNITS PER SF				
105S4	3300	SY,CONCRETE SIDEWALK - 4" THICK PER SY				
105S6	2100	SY,CONCRETE SIDEWALK - 6" THICK PER SY				
116	1	LS,PROJECT SURVEY AND STAKEOUT FOR PER LS				
121AS	400	CY,TOPSOIL FURNISHED AND PLACED PER CY				
123LS	1	LS,SEEDING ON PREPARED AREAS PER LS				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'C' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
205	15500	LF,SAWCUTTING PAVEMENT AND SIDEWALK PER LF				
645.5102	370	SF,GROUND MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 30 SF WITH Z-BARS PER SF				
645.81	100	EA,TYPE "A" SIGN POSTS PER EA				
647.01	47	EA,REMOVAL OF SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.11	9	EA,RELOCATING SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.13	1	EA,RELOCATING TRAFFIC SIGNS, SIZE 'B' (21 TO 40 SF) PER EA				
685W	64000	LF,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
685WS	118	EA,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT SYMBOLS FOR PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK

CAPITAL PROGRAM 5539

ITEMIZED PROPOSAL

OPTION 'C' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
685Y	48000	LF,YELLOW THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
		Subtotal Option 'C' Items:	$			
		Subtotal Base Items:	$			
		Subtotal for Alternate 3: Base Items Plus Option 'C' Items:	$			
1M	NEC	MOBILIZATION MUST NOT EXCEED 4% OF SUBTOTAL SHOWN ABOVE. SEE SPECIFICATION FOR THIS ITEM. PER LS				
		Total Sum Bid for Alternate 3: Base Items Plus Option 'C' Items Plus Mobil.:	$			

SUBTOTAL ITEMS W/MOBILIZATION IN WORDS: _____

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

OPTION 'D' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
1SB	1	LS,CLEARING AND GRUBBING PER LS				
2AS	1	LS,UNCLASSIFIED EXCAVATION PER LS				
4S	3650	CY,STABILIZED SOIL AGGREGATE SUBBASE PER CY				
6EOS-B	1	LS,ENGINEER'S OFFICE, TYPE B PER LS				
30C	70200	LB,FRAMES AND GRATES - CASTINGS PER LB				
30F	21500	LB,FRAMES AND GRATES FABRICATED PER LB				
51D	160	TON,ASPHALT CONCRETE FOR DRIVEWAYS PER TON				
51FX	16440	TON,ASPHALT CONCRETE PER TON				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

OPTION 'D' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
51PRA	50000	SY,COLD MILLING, SHAPING AND REMOVAL OF PER SY				
70B	3820	GAL,BITUMINOUS MATERIAL EMULSION TACK COAT PER GAL				
76SX	1	LS,MAINTENANCE AND PROTECTION OF TRAFFIC PER LS				
80C	800	TON,RIP RAP PER TON				
97A	15270	LF,CONCRETE CURB, TYPE 'A' PER LF				
97B	2170	LF,CONCRETE CURB, TYPE 'B' PER LF				
103	2	EA,ALTERING CATCH BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				
103AD	8	EA,ADJUSTING CATCH BASINS, LEACHING BASINS, FIELD INLETS, MANHOLES, AND DROP INLETS PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

OPTION 'D' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
104B	26	EA,CLEANING EXISTING CATCH BASINS, MANHOLES, DROP INLETS, AND LEACHING BASINS PER EA				
104C	2780	LF,CLEANING CULVERTS AND STORM DRAINAGE PIPE PER LF				
105DW	800	SF,EMBEDDED DETECTABLE WARNING UNITS PER SF				
105S4	3600	SY,CONCRETE SIDEWALK - 4" THICK PER SY				
105S6	2490	SY,CONCRETE SIDEWALK - 6" THICK PER SY				
105SCI4	980	SY,INTEGRALLY COLORED AND IMPRINTED CONCRETE SIDEWALKS, 4" THICK PER SY				
105SCI6	320	SY,INTEGRALLY COLORED AND IMPRINTED CONCRETE SIDEWALKS, 6" THICK PER SY				
116	1	LS,PROJECT SURVEY AND STAKEOUT FOR PER LS				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

OPTION 'D' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
121AS	540	CY,TOPSOIL FURNISHED AND PLACED PER CY				
123LS	1	LS,SEEDING ON PREPARED AREAS PER LS				
205	19500	LF,SAWCUTTING PAVEMENT AND SIDEWALK PER LF				
645.5102	420	SF,GROUND MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 30 SF WITH Z-BARS PER SF				
645.5201	20	SF,GROUND MOUNTED SIGN PANELS W/O Z BARS, HIGH VISIBILITY SHEETING PER SF				
645.81	120	EA,TYPE "A" SIGN POSTS PER EA				
647.01	59	EA,REMOVAL OF SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				
647.11	10	EA,RELOCATING SIGNS - SIZE A (0 TO 10 SQUARE FEET) PER EA				

CARRIED FORWARD _____

IMPROVEMENTS TO CR 7, WICKS ROAD, FROM THE VICINITY OF BLUE JAY DRIVE TO THE VICINITY OF CR 13, FIFTH AVENUE

TOWN OF ISLIP, SUFFOLK COUNTY, NEW YORK
CAPITAL PROGRAM 5539
ITEMIZED PROPOSAL

OPTION 'D' ITEMS

ITEM NO.	APPROX. QUANTITY	ITEM W/ UNIT BID PRICE WRITTEN IN WORDS	UNIT BID PRICE		AMOUNT BID	
			DOLLARS	CENTS	DOLLARS	CENTS
647.13	2	EA,RELOCATING TRAFFIC SIGNS, SIZE 'B' (21 TO 40 SF) PER EA				
685W	66200	LF,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				
685WS	118	EA,WHITE THERMOPLASTIC REFLECTORIZED PAVEMENT SYMBOLS FOR PER EA				
685Y	49600	LF,YELLOW THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS FOR PER LF				

Subtotal Option 'D' Items: $

Subtotal Base Items: $

Subtotal for Alternate 4: Base Items Plus Option 'D' Items: $

1M	NEC	MOBILIZATION MUST NOT EXCEED 4% OF SUBTOTAL SHOWN ABOVE. SEE SPECIFICATION FOR THIS ITEM. PER LS				

Total Sum Bid for Alternate 4: Base Items Plus Option 'D' Items Plus Mobil.: $

SUBTOTAL ITEMS W/MOBILIZATION IN WORDS: _____

CARRIED FORWARD _____

ITEM 80C - RIP-RAP

DESCRIPTION. Under this item the Contractor shall furnish and place rip-rap as shown on the plans or as ordered by the Engineer.

MATERIALS. Rip-rap shall consist of durable field or quarry stone each shaped as nearly as practicable in the form of a right rectangular prism. The stone shall be Scalped Primary Crusher Run Broken Stone consisting of a mixture of stone varying uniformly from 5 pounds to 50 pounds apiece and shall meet the requirements for Type A, B or C of Materials of Construction, M4-Coarse Aggregate.

CONSTRUCTION DETAILS. The rip-rap shall be placed in the areas and to the lines and grades shown on the plans.

METHOD OF MEASUREMENT. The quantity of rip-rap to be paid for under this item will be the number of TONS placed in the work within the payment lines shown on the plans.

BASIS OF PAYMENT. The unit price bid per TON shall include the cost of furnishing all labor, material and equipment necessary to complete the work.

ITEM NO 105DW EMBEDDED DETECTABLE WARNING UNITS

DESCRIPTION: Under this item the Contractor shall furnish and install embedded detectable warnings on sidewalk curb ramps and other locations as shown on the plans or as directed by the Engineer.

MATERIALS: The embedded detectable warning units shall conform to the dimensions shown on the current standard sheet for detectable warnings, or as ordered by the Engineer.

Units shall be composed of cementitious materials, steel, iron, clay, shale, plastics, polymeric materials, resins, pigments, and shall be approved and listed on the New York State Department of Transportation List of Approved Materials – Embedded Detectable Warning Units. The units shall be an approximate visual match to the color specified in the plan, or as ordered by the Engineer. Units shall provide the required contrast (light-on-dark or dark-on-light) with the adjacent curb ramp or other applicable walkways. The units shall be uniform in color and texture, be free of cracks or other defects, and have clean-cut and well defined edges. If no color is specified, the color shall be dark gray Federal Standard 595B #36081 or darker.

The detectable warning units shall meet the following physical properties:
Compressive Strength, minimum 28 days, 55 MPa minimum
Freeze-thaw Loss (25 Cycles, one per day, 10% NaCl solution), 1.0 % Maximum

Embedded detectable warning units shall be shipped and packaged in accordance with commercially accepted standards. The following information shall be marked on each package or on the shipping invoice: the name of the product, the name and address of the manufacturer, and the quantity of material.

Acceptance of this material will be based on the manufacturer's name appearing on the New York State Department of Transportation List of Approved Materials – Embedded Detectable Warning Units.

The Contractor shall submit a sample unit for approval by the Engineer prior to beginning work.

CONSTRUCTION DETAILS: Setting bed material and / or surface preparation materials for installation of detectable materials units shall be in accordance with the manufacturer's recommendations. Embedded detectable warning units may be installed in plastic concrete, installed directly on existing subbase prior to placing concrete, inlaid on prepared concrete surfaces or as otherwise directed by the manufacturer or specified in the Contract documents.

Follow all applicable manufacturers' requirements for environmental conditions, surface preparation, installation procedures, curing procedures, and materials compatibility.

METHOD OF MEASUREMENT: The quantity to be paid for under this item will be the number of square feet of embedded detectable warning unit installed in accordance with these specifications and as ordered by the Engineer.

BASIS OF PAYMENT: The unit price bid per Square Foot shall include the cost of furnishing all labor, materials and equipment to complete the work, including bedding material. No adjustment shall be made for concrete removed to accommodate embedded units.